

BILL OF QUANTITIES

NAME OF WORK: Estimate For Flooring Work Chemistry Lab, Physic Lab, Store Room, Computer Lab, Nano Research Lab, Physics Lab Room No-40, Dark Room And Physical Chemistry Lab At Magdh Mahila College, P.U. Patna

Estimated cost:Rs.11,68,000/-					Date of Receiving Tender : 30.06.2021			
Earnest Money Required: Rs. 24,900/-					Time of completion : 3 Month			
Cost of B.O.Q. :Rs.2,500/-					M.R. No and date			
S.N.	Code No	Description	QUANTITY		Unit	Rate (Rs.)	Amount	
1	M.R	providing labour for making rough surface for laying floor tiles as per direction of e/i.	68	sqm	each	400	27200	
2	11.41.2	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption's less than 0.08% and conforming to IS: 15622 of approved make in all colours and shades, laid on 20 mm thick cement mortar 1:4 (1 cement: 4 coarse sand) including grouting the joint with white cement and matching pigments etc., complete.						
			N	L	W	H		
		Chemistry lab room no - 46	1	14.53	10.8		156.92	
		deduct table area	-8	2.9	1.42		-32.94	
			-2	4.09	0.71		-5.81	
			-2	1.07	0.71		-1.52	
		door area	5	1.22	0.3		1.83	
		Scarting	2	14.53	0.15		4.36	
			2	10.8	0.15		3.24	
		Phuysics lab	1	14.53	10.78		156.63	
		Scarting	2	14.53	0.15		4.36	
			2	10.78	0.15		3.23	
		Door area	4	1.22	0.3		1.46	
		Bath room+office room	1	4.92	3.53		17.37	
		Scarting	2	4.92	0.15		1.48	
			2	3.53	0.15		1.06	
		Door area	2	1.22	0.3		0.73	
		Store room	1	5.34	3.53		18.85	
		Scarting	2	5.34	0.15		1.60	
			2	3.53	0.15		1.06	
		Door area	2	1.22	0.3		0.73	
		Computer room	1	5.33	3.43		18.28	
		Scarting	2	5.33	0.15		1.60	
			2	3.43	0.15		1.03	
		Door area	2	1.22	0.3		0.73	
		room no-40	1	10.77	1.81		19.49	
		Scarting	2	10.77	0.015		3.23	
			2	1.81	0.15		0.54	
			1	1.22	0.3		0.37	
		Physics lab -2R.N. -50	1	10.78	10.58		114.05	
		Scarting	2	10.78	0.15		3.23	
			2	10.58	0.15		3.17	
		Door area	2	1.22	0.3		0.73	
		Dark Room No 52	1	7.71	2.48		19.12	
		Scarting	2	7.71	0.15		2.31	
			2	2.48	0.15		0.74	
Physical Chemistry Lab	1	14.33	10.75		154.05			
Scarting	2	14.33	0.15		4.30			
Door area	1	1.22	0.3		0.37			
Deduct table area	-2	7.27	1.45		-21.08			
	-1	3.58	1.47		-5.26			
TOTAL AMOUNT OF ESTIMATE							1167998	

I do agree to do the work on (a) or estimated rate

(b)% below on estimated rate

.....% above on estimated rate

(c)

Name and address of contractor

Kindly visit office to purchase Tender Papers, BOQ with terms and conditions

