

**OFFICE OF THE PRINCIPAL
MAGADH MAHILA COLLEGE
NORTH OF GANDHI MAIDAN
PATNA 800001**

website: www.magadhmahilacollege.org, Telephone: 0612-2219454

Copy Bee Notice Board

Quotation No: P/MMC/957 **EMERGENT NOTICE INVITING QUOTATION**

Date: 10/12/2025

**NAME OF WORK: RE ROOFING OF BOTH STAIRCASES OF VOCATIONAL BUILDING OF MAGADH
MAHILA COLLEGE, P.U. PATNA**

Sealed quotations are invited in prescribed format for this work, along with the amount of Earnest Money Deposit, as mentioned in the Terms and Conditions of this notice. For details terms and condition, please visit the office of the undersigned on any working days from 10.30 A.M. to 5.00 P.M. or website of College.

Designation of officer inviting quotation	Principal, Magadh Mahila College, Patna
Place, Time & Date of receiving of quotation	Office of the Principal, Magadh Mahila College, Patna up to 3.00 p.m. on 19/12/2025.
Place, Time & Date of opening of quotation	Office of the Principal, Magadh Mahila College, Patna at 3.30 p.m. on 19/12/2025.

PREScribed FORMAT

S.N.	Code No	Description	Quantity		Unit	Rate	Amount
						(Rs.)	
1	15.7.4	Demolishing brick work including stacking of serviceable material and disposal of unserviceable material within 50 meters lead: In cement mortar	3	Cum	Cum		
2	6.1.1 2/1	Brick work with bricks of class designation 100A in foundations and plinth in : Cement mortar 1 :4 (1 cement: 4 coarse sand)	2	Cum	Cum		
3	6.3A	Extra for Brick work in superstructure above plinth level upto floor V cum	2	Cum	Cum		
4	6.18.4A	Half brick masonry with bricks of class designation 100A in foundations and plinth in : Cement mortar 1:4 (1 cement: 4 coarse sand)	7	Sqm	Sqm		
5	6.19 A	Extra for half Brick masonry in superstructure above pinth level upto floor V level	7	Sqm	Sqm		
6	13.11.2	Cement plaster in course sand- 12 mm cement plaster of mix: 1:4(1 cement :4 coarse sand)	17	Sqm	Sqm		
7	13.12.2	Cement plaster in course sand, 15 mm cement plaster on rough side of single or half brick wall of mix, 1:4(1 cement: 4 coarse sand)	23	Sqm	Sqm		
8	13.46.1	Finishing walls with Acrylic Smooth exterior paint of required shade :New work (Two or more coat applied @ 1.67 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	40	Sqm	Sqm		


S.N.	Code	Description	Quantity		Unit	Rate	Amount
	No						
9	13.80	Removing dry or oil bound distemper by scrapping, sand paper and preparing the surface smooth including necessary repair scratches etc. complete.	183	Sqm	Sqm	(Rs.)	
10	14.66 .1	Finishing walls with Acrylic Smooth exterior paint of required shade: Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing cement paint surface	183	Sqm	Sqm		
11	15.28 .1	Dismantling roofing including ridges, hips valleys and gutters etc. and stacking the material within 50 metres lead of: G.S. Sheet	28	Sqm	Sqm		
12	10.1.	Structural steel work in singal section fixed without connecting plate including cutting .hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	80	Kg	Kg		
13	12.65 X.2	Providing & fixing at all heights, levels and locations colour finish Aluminium alloy roofing sheets of alloy IS designation 31500, temper Hx8 conforming to IS 737 and dimensions as per IS code 2676 with characteristics of good formability and corrosion resistance. The profile sheets shall be fixed to truss members inslope or required pitch or curvature with Hex capheaded self drilling /tapping Stainless steel screws M6, 60mm long with 3 mm EPDM sealwasher etc. all inclusive of labour, scaffolding, T&P and sundries etc. complete as per directions of the Engineer-In Charge. {Cost of truss/frame work shall be paid separately).	56	Sqm	Sqm		
14	13.81 .3	Applying priming coat: With ready mixed zinc chromate yellow primer of approved brand and manufacture on steel galvanized iron/steel works	30	Sqm	Sqm		
15	13.93 .1	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade: Two or more coats on new work,	40	Sqm	Sqm		
16	P.M.R	Providing electrical welding machine for spot welding including cairrage of machine and labour charges all complete, for the minor repair of existing grill gates at roof, as per direction of Engineer-in-charge.	1	Day	Day		
17	S.O.R	Carriage of materials					
a		Designation 100 A bricks from 8 Km distance of surface road	1200	No	%0No		
b		Sone sand from Koelwar, 45 Km distance of surface road	2	Cum	Cum		

S.N.	Code No	Description	Quantity	Unit	Rate	Amount
18	S.O.R	Price difference of materials for Patna urban area: as prescribed in the Schedule of rates.				(Rs.)
a		Designation 100 A bricks				
b		Cement	1200	No	%0No	
19		Reserved price for any other un seen work.	12	Bag	Bag	
		Total Amount	1	L.S.	L.S.	3708 3708

Terms and conditions:

- 1 Earnest Money Deposit in the form of Bank Draft in the favour of Principal, Magadh Mahila College, Patna or N.S.C./ Time Deposit of Post Office , duly pledged in the name of Principal, Magadh Mahila College, Patna @ 2% i.e.Rs.3300/- is essentialy required with quotations. Remaining amount of Security Deposits @ 8% of bill amount will be deducted from bill.
- 2 The rate and amount of item vide serial number 19 has been fixed as Rs.3708/- only.
- 3 Work must be completed within 45 days after receiving work order.
- 4 Any registered agency of Government of Bihar / C.P.W.D. /M.E.S. will be considered.
- 5 Any working agency of Works Department, Patna University, Patna will also be considered for the works of Rs. 1,00,000 and under.
- 6 Payment will be considered after satisfactory completion of work and after submitting satisfactory work completion certificate.
- 7 The undersignd reserve the right to accept or reject any or all the qootations without assigning any reason.
- 8 All disputes, what so ever shall be reffered to the sole arbitration of the Principal, Magadh Mahila College, Patna and his decision shall be final and binding on the agency.

P. C. K. K.
05/12/25.


10.12.25
PRINCIPAL,
MAGADH MAHILA COLLEGE, PATNA
Principal
Magadh Mahila College
Patna