



OFFICE OF THE PRINCIPAL
MAGADH MAHILA COLLEGE
NORTH OF GANDHI MAIDAN
PATNA 800001

website: www.magadhmahilacollege.org, Telephone: 0612-2219454

EMERGENT NOTICE INVITING QUOTATION

Quotation No: P/MMC/41

Date: 15-01-2026

NAME OF WORK: REPAIR AND PAINTING AT DEPARTMENT OF MUSIC, MAGADH MAHILA COLLEGE, P.U. PATNA

Sealed quotations are invited in prescribed format for this work, along with the amount of Earnest Money Deposit, as mentioned in the Terms and Conditions of this notice. For details terms and condition, please visit the office of the undersigned on any working days from 10.30 A.M. to 5.00 P.M. or website of College.

Designation of officer inviting quotation	Principal, Magadh Mahila College, Patna
Place, Time & Date of receiving of quotation	Office of the Principal, Magadh Mahila College, Patna up to 3.00 p.m. on 28/01/2026.
Place, Time & Date of opening of quotation	Office of the Principal, Magadh Mahila College, Patna at 3.30 p.m. on 28/01/2026.

PRESCRIBED FORMAT

S.N	Code No	Description	Quantity		Unit	Rate	Amount
						(Rs.)	
1	14.1.2	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge. With cement mortar 1:4 (1 cement: 4 coarse sand)	18	Sqm	Sqm		
2	13.80	Removing dry or oil bound distemper by scrapping, sand paper and preparing the surface smooth including necessary repair scratches etc. complete.	372	Sqm	Sqm		
3	13.7.2	Providing and applying white cement based putty of average thickness 2 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	40	Sqm	Sqm		
4	13.4.6.1	Finishing walls with Acrylic Smooth exterior paint of required shade: New work (Two or more coat applied @ 1.67 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	40	Sqm	Sqm		
5	14.6.6.1	Finishing walls with Acrylic Smooth exterior paint of required shade: Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing cement paint surface	350	Sqm	Sqm		

P. K. Singh
07/01/26

15-01-26

S.N	Code No	Description	Quantity		Unit	Rate	Amount
						(Rs.)	
6	13.9 3.2.	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade. One or more coats on old work.	108	Sqm	Sqm		
7	8.2.2 .1	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations, of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand); joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels. Granite of any colour and shade -Area of slab upto 0.50 sqm	2	Sqm	Sqm		
8	9.12 7.1	Providing & Fixing decorative high pressure laminated sheet of plain / wood grain in gloss / matt / suede finish with high density protective surface layer and reverse side of adhesive bonding quality conforming to IS : 2040 Type S, including cost of adhesive of approved quality 1.5 mm thick	4	Sqm	Sqm		
9		Providing following materials of approved quality and workers for necessary repair of wooden doors, windows and tables, as per direction of Engineer-in-charge.					
a	o111	Carpenter class 1					
b	1247	Adhesive rubber base	3	Day	Day		
c	2413	12 mm commercial ply	2	Kg	Kg		
d	o685	Oxidised mild screws 25 mm	4	Sqm	Sqm		
10	S.O. R.	Carriage of materials: Sone sand from Koelwar, 45 Km distance of surface road.	50	No	%No		
11	S.O.R	Price difference of materials for Patna urban area.	0.4	Cum	Cum		
12		Reserved amount for any other unseem work.	6	Bag	Bag		
		Total Amount	1	L.S.	L.S.	223	223

Terms and conditions:

- 1 Earnest Money Deposit in the form of Bank Draft in the favour of Principal, Magadh Mahila College, Patna or N.S.C./ Time Deposit of Post Office, duly pledged in the name of Principal, Magadh Mahila College, Patna @ 2% i.e. Rs.1400/- is essentially required with quotations. Remaining amount of Security Deposits @ 8% of bill amount will be deducted from bill.
- 2 The rate and amount of item vide serial number 12 has been fixed as Rs.223/- only.
- 3 Work shall be completed within 45 days after receiving work order.
- 4 Any registered agency of Government of Bihar (C.P.W.D./M.E.S.) will be considered.
- 5 Any working agency of Works Department, Patna University, Patna will also be considered for the works of Rs. 1,00,000 and under.
- 6 Payment will be considered after satisfactory completion of work and after submitting satisfactory work completion certificate.
- 7 The undersigned reserve the right to accept or reject any or all the quotations without assigning any reason.
- 8 All disputes, what so ever shall be referred to the sole arbitration of the Principal, Magadh Mahila College, Patna and his decision shall be final and binding on the agency.

PRINCIPAL,

MAGADH MAHILA COLLEGE, PATNA